CORRIGENDUM 01 Dated 09.01.2024

Tender Notice No.: 22/2023-24 Dated 01.01.2024

Name of Work: Supply, Installation, Testing, Commissioning, Operations & Maintenance of City Surveillance & Traffic Management System with Command & Control Centre in S.A.S Nagar City, Punjab.

The following amendments have been made in the RFP:-

Sr. No.	RFP Section/ Clause No.	Section Name	Existing	Amended
1	**Section-III**	**DETAILED SPECIFICATIONS:**		
i	**3.3**	**Outdoor RLVD 2MP Bullet/ Box Camera with all accessories:**		
	4	Lens	2.7-13.5 mm or better, Megapixel Lens with remote zoom and focus, P-IRIS lens,	2.8-12 mm or better, Megapixel Lens with remote zoom and focus, DC /P-IRIS lens
ii	**3.4**	**IP HD 2MP PTZ Camera with all accessories**		
	6	Optical Zoom	Zoom: 40x optical, 12x digital	Zoom: 35x optical, 12x digital
	41	IR illumination (Internal/ External)	Optimized IR with power-efficient, long life 850 nm IR LEDs Range of reach 250 m or more depending on the scene	Optimized IR with power-efficient, long life 850 nm IR LEDs Range of reach 200 m or more depending on the scene
iii	**3.5**	**Outdoor IP 4MP Surveillance Bullet/ Box Camera with all accessories**		
	4	Lens	2.7~13.5 mm or better, IR corrected, Megapixel Lens with remote zoom and focus	2.8-10 mm or better, Megapixel Lens with remote zoom and focus, DC /P-IRIS lens
iv	**3.45**	**Enterprise & Network Management System**		
	6	**Network Fault Management**	(xii) The system should support Netconf, Streaming telemetry, MQTT protocols for monitoring	The system should support Netconf, Streaming telemetry
	8	**Monitoring Features – Servers & Virtualization**	ii) OEM of proposed NMS software application shall have ISO 9001:2015, ISO 27034-1, ISO 27001:2013 and ISO 45001:2018	OEM of proposed NMS software application shall have ISO 9001:2015, ISO 27034-1, ISO 27001:2013

v	3.7	**Industrial grade Field Layer-2, 8 port POE Switch with Ethernet surge protection**		
	9	Certification	RoHS Compliant, IEEE 802.3af, 802.3at, NTP	RoHS Compliant, IEEE 802.3af, 802.3at, NTP/ SNMP
vi	3.30	**24 Port Managed L3 Core Switch for Command Centre**		
	1	**General Requirements**	Should have 880 Gbps of Switching capacity or more	Should have minimum 600 Gbps of Switching capacity or more
			Should have 654 Mbps of Packets Forwarding or more	Should have minimum 300 Mbps of Packets Forwarding or more
			Should support multiple configuration files with 2 bootable partitions for better availability and easy upgrade / fall back.	Should support multiple configuration files with 2 bootable partitions/ software files for better availability and easy upgrade / fall back.
	2	**Layer 2 Requirements**	Should support MCLAG (Multi Chassis Link Aggregation)/VSS Support.	Should support MCLAG (Multi Chassis Link Aggregation)/ LAG/ VSS Support.
	3	**Layer 3 Requirements**	Should support Unicast Reverse Path Forwarding/ RPF, IPv6 route filtering	Should support Unicast Reverse Path Forwarding/ RPF/ IPv6 route filtering
vii	3.31	**24 Port Managed L2 Aggregation Switch for Command Centre**		
	2	***Layer 2 Requirement***	Should support MCLAG (Multi Chassis Link Aggregation) or LACP (Link aggregation Control Protocol)	Deleted

10/1/23

Chief Engineer
For Managing Director