Name of work: Supply, Installation, Testing, Commissioning, Operations & Maintenance of City Surveillance & Traffic Management System with Integrated Command & Control Centre in S.A.S. Nagar, Punjab

Tender Notice No.22/2023-24 Dated 01.01.2024

Name of bidder: _____

5.2) PRICE COMPONENT FOR CAPEX (INCLUDING COMPREHENSIVE WARRANTY FOR 01 YEAR FROM THE DATE OF GO-LIVE) INCLUDING MANPOWER:

(TO BE UPLOADED IN PDF FORMAT)

S. No	ITEM	UNIT	QTY	UNIT BASE PRICE (EXC. GST)	TOTAL PRICE (INR)	GST	TOTAL PRICE INCLUDING TAXES (INR)
			A	B	C (AxB)	D	C+D
A	**Field Locations:**						
1.	SITC of Outdoor ANPR 2MP Box Camera with all accessories and external IR illuminator	Each	216				
2.	SITC of Outdoor ANPR 2MP Bullet/ Box Camera with all accessories and external IR illuminator (For SVD)	Each	16				
3.	SITC of Outdoor RLVD 2MP Bullet/ Box Camera with all accessories	Each	63				
4.	SITC of RADAR/ Video Based Speed Violation Detection System for both sides i.e. To and Fro for 3 or 4 lane road including Traffic Management software with licences suitable for achieving desired accuracy during day/ night and in all weather conditions, complete with following items:- - RADAR-as required - PLB/ HDPE/ Flexible pipes from RADAR/ cameras to Main Outdoor Cabinet box (At junctions) - Armoured Cat-6 cables, Armoured Optical Fibre Cable, Power cabling from RADAR/ cameras to Main Outdoor Cabinet box, underground/ on surface (At junctions), - Termination boxes, - Managed L2 Network switches (Industrial grade), Passive items i.e. LIUs, Pigtails, Patch cords on Poles.	Locations	02				

	- Any other item, if required to made the system operational to achieve the desired functionality. **Note:** ITMS Server, ANPR Cameras, Poles, Outdoor Cabinet boxes, Network switches & LIUs, LPUs in Main Outdoor Cabinet boxes, UPS & earthing excluded. It is mandatory to provide ANPR with Global Shutter for SVD system. (Attach item wise unpriced BOQ for all locations in Technical Bid)						
5.	SITC Outdoor IP 4MP Surveillance Bullet/ Box Camera with all accessories	Each	104				
6.	SITC of IP HD 2MP PTZ Camera with all accessories	Each	22				
7.	SITC of Manageable Layer-2 Industrial grade Switch 8 Port PoE with surge protection	Each	23				
8.	SITC of Manageable Layer-2 Industrial grade Switch 24 Port PoE with surge protection	Each	18				
9.	SITC of Industrial grade Local Processing Unit (LPU)	Each	72				
10.	SITC of 1KVA Online UPS for Outdoor Junction (120 minutes battery backup)	Each	41				
11.	SITC of 2KVA Online UPS for Outdoor Junction (120 minutes battery backup)	Each	02				
12.	SITC of Outdoor Cabinet Box with Accessories	Each	41				
13.	SITC of Termination Box with Accessories	Each	91				
14.	SITC of 6.3Mtr Octagonal Pole with foundation (with 6mtr Single Arm)	Each	49				
15.	SITC of 6.3Mtr Octagonal Pole with foundation (with 8mtr Single Arm)	Each	35				
16.	SITC of 6.3Mtr Octagonal Pole with foundation (with 8mtr Double Arm)	Each	07				
17.	SITC of 4 mtr long Pole with foundation	Each	72				
18.	SITC of 8 mtr long Pole with foundation	Each	22				
19.	SITC of 3 Core 1.5mm Armoured copper cables	Mtrs	12000				
20.	SITC of 2 Core 10 sqmm Armoured aluminum cables	Mtrs	6000				
21.	SITC of 6 Core Optical fibre cables (OFC)	Mtrs	3000				
22.	SITC of Cat 6 Armoured cables	Mtrs	11000				
23.	SITC of PLB HDPE duct in trenchless laying	Mtrs	7500				
24.	SITC of Electricity Meter with outdoor enclosure	Each	22				
25.	SITC of G.I Rod earth System	Each	162				

26.	SITC of Passive Components for field locations i.e. LIUs, Pigtail, OFC/Cat 6 patch cords etc.	Lots	23				
B	**Data Centre and Integrated Command & Control Centre:**						
1.	SITC of IR IP Indoor dome cameras	Each	05				
2.	SITC of Firewall for network protection in N+1 configuration	Each	02				
3.	SITC of Rack mount Servers for Video Management in N+1 configuration with OS, MS office & any application	Each	06				
4.	SITC of Video Analytics server	Each	01				
5.	SITC of Video Management Software	Lot	01				
6.	SITC of Video Analytics software	Lot	01				
7.	SITC of Traffic Management software with e-Challan module	Lot	01				
8.	SITC of External enterprise grade storage for recording data with usable space for 35 days (Minimum 1000TB)	Lot	01				
9.	SITC of PTZ 3-axis Joystick Controller with LED display. Same make of PTZ camera	Each	05				
10.	SITC of 42 U Network Racks with KVM	Each	03				
11.	SITC of Operator Workstations with dual monitors	Each	10				
12.	SITC of 24 Port Managed L3 Network Switch	Each	02				
13.	SITC of 24 Port aggregation L2 Managed Network switch	Each	02				
14.	SITC of Passive Components for Command & Control Centre/ Server Room i.e. IO's, face plates, LIUs, Pigtail, HDMI Cables OFC/ Cat 6 patch cords etc. as required to make the system operational	Lot	01				
15.	SITC of 55" LED Video display	Each	01				
16.	SITC of 55" LED based Video Wall with Controller in 5x2 grid	Set	01				
17.	SITC of Multi-function Laser Printer	Each	01				
18.	SITC of 2x20 KVA UPS with battery backup of 01 Hr	Each	01				
19.	SITC of 62 KVA DG set in soundproof canopy	Each	01				
20.	SITC of 2x5 TR Precision Airconditioning for Data Centre in redundant mode	Each	01				
21.	SITC of 2.0 Ton rating split AC	Each	02				
22.	Timer for 2 nos. Split ACs	Each	01				
23.	SITC of Chemical Earthing system	Each	04				
24.	Providing & Fixing of antistatic Raised flooring with suitable pedestal assembly.	Sft	400				

25.	SITC of Biometric Access Control System (For 6 nos. doors) complete with controller, readers and cards etc.	System	01				
26.	SITC of Anti-Virus end point software suite for servers, workstations, Local processing units and any other devices (Valid upto 3 years after Go-live)	Lot	01				
27.	Establishment of Enterprise & Network Management System (EMS & NMS) for monitoring and measurement of the SLA parameters identified for the project	Job	01				
	NOTE:- All components will be covered under free Comprehensive AMC for 12 months, by deploying minimum 01no. Project Manager and 04 nos. field Engineers including T&P and sky lift as required. Any additional manpower, if required to maintain SLA will be provided by the SI at his own cost.						
	Sub Total-1:						

Price (in words) _____

NOTE:- Total amount of table 5.2 should be filled in Price Bid (xls file).

Name of work: Supply, Installation, Testing, Commissioning, Operations & Maintenance of City Surveillance & Traffic Management System with Integrated Command & Control Centre in S.A.S. Nagar, Punjab

Tender Notice No.22/2023-24 Dated 01.01.2024

Name of bidder: _____

5.3) PRICE COMPONENT FOR OPEX AND MPLS CONNECTIVITY, INCLUDING MANPOWER:

(TO BE UPLOADED IN PDF FORMAT)

S. NO.	ITEM	UNIT	QTY	UNIT BASE PRICE (EXC. GST)	TOTAL PRICE (INR)	GST	TOTAL PRICE INCLUDING TAXES (INR)
			A	B	C (AxB)	D	C+D
A	**Annual comprehensive Maintenance:**						
1	Annual comprehensive Maintenance for 2 years for all equipment mentioned above (Table 5.2), after expiry of free AMC of One year, including deployment of minimum manpower, required tools and plants and sky lift as required. Any additional manpower, if required to maintain SLA will be provided by the SI at his own cost.						
i	For 1st Year after expiry of free AMC of One Year	Job	01				
ii	For 2nd Year after expiry of free AMC of One Year	Job	01				
B	**MPLS Connectivity:**						
1	MPLS connectivity at Edge locations with required bandwidth & redundancy connected with Command & Control Centre						
i	For First year from the date of Go-Live.	Locations	20				
ii	For Second year from the date of Go-Live.	Locations	20				
iii	For Third year from the date of Go-Live.	Locations	20				
2	MPLS connectivity with required bandwidth at Command & Control Centre						
i	For First year from the date of Go-Live.	Location	01				
ii	For Second year from the date of Go-Live.	Location	01				

iii	For Third year from the date of Go-Live.	Location	01				
	Sub Total-2						

Price (in words) _____
NOTE:-

Note: Total amount of table 5.3 should be filled in Price Bid (xls file).